Scope of the Work:

The following scope of work identifies the tasks and responsibilities that the qualifying Company/Firm shall deliver upon, by working closely with the Network & Infrastructure Department of PRAL:

Scope of Work (Procurement of Servers)

The scope of work includes supply, installation, commissioning and maintenance of Servers as per the BOQ with onsite support for a period of 5 years warranty including parts and labour.

The equipment quoted by bidder should not be declared as EOL or EOS by the OEM within the contract period. In the event of the supplied equipment being declared as EOL or EOS within the period of 5 years from the date of commissioning of the equipment, the bidder must replace the equipment with equipment having equivalent or higher configurations.

The selected Bidder shall appoint a single point of contact, with whom PRAL will deal with, for any activity pertaining to the requirements of this RFB. Provide documentation and template for conducting UAT (User Acceptance test).

Server Specifications:

Processor

- 2 x Intel® Xeon® Gold 65xxY+ Processor
- 60 MB Cache
- Cores: 32
- Total Cores: 64
- Clock Speed: 2.1GHz – 3.1GHz
- TDP: 250W
- Intel® latest chipset

Memory (RAM)

- **Installed Memory:** 1TB DDR5 ECC with dual rank supported or higher.
- **Scalability:** Each server must have the capacity to be scalable up to 2 TB or more through additional DIMMs, without requiring any additional memory expansion hardware.
- **Error-Correcting Code (ECC)**: Enabled for reliability.

Primary Storage

- **Operating System Drives**:
    - **2 x 256 GB NVMe SSDs** for OS installation. N.2
- **Data Storage Drives**:
    - **6 x 1TB SAS**, hot-swappable.

Storage Scalability

- Builtin Additional storage bays available for future expansion.

RAID Configuration

- Integrated RAID controller with support for:
    - RAID Levels: **1, 5, 6, 10**.
    - Online RAID expansion capability.

Network Interfaces

- 2 × 25Gbps SFP28 ports, backward compatible with 10Gbps, including compatible SFP28 transceivers.
- 4 x 10 Gbps Ethernet Ports. Auto negotiable to 1 Gbps
- 1 x 1Gbps Management/ILO Port.

HBA Cards

- 2 HBA NVMe Ready cards with dual ports of 32Gbps or higher data transmission speed. Auto negotiate to 16 Gbps.

Chassis

- Rack-mounted 2U or 3U server with redundant hot-swappable power supplies and fans

Operating System Support

- Support for all operating systems from Microsoft (X86), Linux, Ubuntu, Solaris Intel, RHEL, SUSE, VMware/Citrix/Oracle/Open, Hypervisors.

Install Media

- Non-licensed Bootable media/ISO Files for latest version Windows and of ESXI with embedded drivers for server Hardware including, HBA, Network and Raid

Post-Sales Support and warranty

- The supplier shall provide comprehensive post-sales support for the entire solution (hardware, software, and licenses) and associated equipment for a period of five (05) years, with 24x7 extendable support. The Original Equipment Manufacturer (OEM) must provide a written commitment to support and services. Dedicated support engineers from the supplier are mandatory, Critical components must be available on-site.
- OEM Must supply the required Servers through its Highest level of Partners in Pakistan.
- The OEM must be in business since last (Ten)10 years for manufacturing, supply & installation of Enterprise grade Rack Mount Servers.
- The manufacturer must have country wide direct support from its Partners including major cities of Pakistan i.e. Islamabad, Lahore and Karachi.
- Bidder must provide evidence from manufacturer to have spare parts in Pakistan with Next business day (NBD) delivery commitment in Islamabad (Documentary evidence required).
- Firmware/software/patches upgrades of equipment must be done proactively during the warranty coverage period. This should be done when stable release of major/minor firmware /software/patches are available. This should also be analyzed at least once a year.
- All equipment should be quoted with 5 years onsite comprehensive warranty including parts and labor / support. No additional charges would be paid on account of parts replacement or labor charges during warranty period of 5 years.
- The installation & configuration should be carried out by certified engineers from the supplier.
- The proposed server OEM shall be positioned in the latest published Gartner Magic Quadrant for the relevant technology category. Documentary evidence shall be provided by the bidder.
- All network ports must be fully populated with the required transceivers (SFP/SFP+/SFP28) or RJ-45 connectors, except for the ports specified as "without SFP's". The supplier/bidder must provide all necessary converters, cables, and transceivers for the populated ports.

BILL OF QUANTITY

TECHNICAL BOQ – Metro Datacenter			
Sr.No	**Equipment Detail**	**U/M**	**QUANTITY**
1.	RACK MOUNT SERVERS (Along with all allied accessories and installation)	No	2

e-Pak Acquisition and Disposal System (EPADS) generated document | © 2026

Delivery & Installation Timelines

- The timeline for the delivery & Installation/commissioning of the Servers is 08-10 weeks which shall start once the Contract is signed or issuance of the purchase/service Order.

TECHNICAL EVALUATION CRITERIA				
Sr #	**Descriptions**	**Total Points**	**Scoring Points**	**Remarks** (Attachment of relevant evidence in each case is mandatory. In case of non-compliance no mark will be awarded)
1	**Client Portfolio/ Relevant Experience**	**20**		
	Supplied & Installed Enterprise grade servers of to more than 10 local/international/multinational clients including public sector or private sector organizations:		**15**	**Documentary proof**: (Purchase/Service order/ copies of contract with contact details of clients should be furnished, along with completion certificates *Multiple projects with same client will be counted as one.
	Supplied & Installed Enterprise grade servers of to more than 06 but less than or equal to 10 local/international/multinational clients including public sector or private sector organizations:		**10**	
	Supplied & Installed Enterprise grade servers of to more than 03 but less than or equal to 06 local/international/multinational clients including public sector or private sector organizations:		**05**	
2	**Compliance to the Technical Specifications and scope of work mentioned in the bidding document**	**40**		
	100% Compliance to the Specifications and scope of work / services mentioned in the bidding document.		40	If the quoted product is fully complied with the specifications mentioned in the Scope of Work, full Marks will be given, else zero (0). (Bidder to share the copies of technical literature, Data Sheet & Brochures from the manufacturer, which

e-Pak Acquisition and Disposal System (EPADS) generated document | © 2026

				may be verified on the Internet)
3	**Presence of the OEM in Pakistan for Warranty & technical Support**	**10**		
	Presence of Principal/OEM in Pakistan for equipment warranty & Support Services		**10**	A Written confirmation from Principal/OEM on their Letterhead is required confirming their presence in Pakistan for equipment warranty & Support services.
4	**Compliance to the delivery timelines for the supply, installation, commissioning of servers**	**15**		
	The Delivery Timelines for the supply, installation, commissioning of servers is 08-10 weeks after issuance of Purchase Order, Bidder to share compliance.		**10**	A written confirmation on Company's letterhead is required**.**
5	**Financial Turnover**	**15**		
	Annual turnover /revenue of the company is greater than or equal to 40 million (PKRs)		15	Documentary proof required (tax returns or financial audited report from registered firm/company for the year 2023-2024 or latest)
	Annual turnover /revenue of the company is less than 40 million (PKRs) but greater than or equal to 30 million (PKRs)		10	
	Annual turnover /revenue of the company is less than 30 million (PKRs) but greater than or equal to 20 million (PKRs)		**5**	
Total Technical Evaluation Score		**100**		

Passing Criteria:

Minimum Qualifying Score: A bidder must obtain a minimum of 70 marks out of 100 in the Technical Evaluation to qualify for further evaluation.
Mandatory Technical Compliance: Full marks (40/40) in Technical Compliance and (10/10) in OEM presence is required, Failure in either shall render the bid technically non-responsive irrespective of the overall score.

All participating vendors are required to submit compliance sheets in editable Excel format against the technical specifications.